

केन्द्रीय बौद्ध विद्यासंस्थान
समविश्वविद्यालय
चोगलमसर, लेह-लद्दाख
E-mail: cibsladakh@gmail.com



དབུས་གཞུང་ནང་པའི་རིག་གནས་གཙུག་ལག་སློབ་གཉེར་ཁང་།
ཚྭ་ཆ་ལ་གྲེས་ཀྱི་སྡེ་ཁག་།

Website: www.cibs.ac.in

Central Institute of Buddhist Studies

(Deemed to be University under Ministry of Culture, Govt. of India)

Choglamsar, Leh-194101, UT of Ladakh

No. CIBS/11/Constr/78 / 3252-56

Dated : 05-10-2026

Tender Notice

Sealed quotations are hereby invited from eligible and experienced contractors for the execution of the extension of ground near the Library building of the University Campus of the Central Institute of Buddhist Studies (CIBS), Choglamsar, Leh.

The Bill of Quantities (BOQ) for the above-mentioned work is enclosed with this Tender Notice vide Annexure - I. The interested contractor (s) shall carefully examine the BOQ and quote the rates against all the items.


The interested contractor(s) shall submit the duly filled and signed quotation on his/her official letterhead, along with the duly filled BOQ, in a sealed envelope addressed to the Office of the Assistant Registrar, CIBS, Choglamsar, Leh.

The quotation should reach to this office within 7 days from the date of issue of this Tender Notice. Quotations received after the stipulated period shall not be considered.

Terms and Conditions

1. The contractor must have a minimum of three (03) years of work experience preferably with the Central Institute of Buddhist Studies (CIBS) in the execution of civil construction, repair and maintenance, or other similar works.
2. The contractor shall submit documentary evidence of the work experience certificate issued by Govt. agencies.
3. Preference will be given to those contractor(s) who are having a satisfactory record of previous works executed for CIBS.
4. The competent authority reserves the right to verify the contractor's previous work record and performance before considering the quotation for acceptance.
5. The contractor shall inspect the site and acquaint himself/herself with the existing site conditions, accessibility, availability of materials, labour requirements and all other factors affecting the execution of the work before quoting the rates.
6. The rates quoted shall be inclusive of labour, materials, tools and plants, transportation, loading/unloading, taxes, duties, royalties and all other incidental charges required for the satisfactory completion of the work.

7. The contractor shall execute the work strictly in accordance with the BOQ, specifications and instructions.
8. The contractor shall ensure the quality of materials and workmanship. Any defective work or material identified during execution shall be rectified/replaced by the contractor at his/her own cost.
9. The work shall be completed within the stipulated period specified in the work order.
10. Payment shall be made on the basis of the actual quantity of work executed and measured at site, subject to satisfactory completion and certification by the Engineer-in-Charge.
11. The contractor shall maintain proper safety measures at the work site and shall be responsible for the safety of his/her workers, materials and equipment during execution of the work.
12. Any quotation which is incomplete, conditional, or does not comply with the prescribed terms and conditions may be rejected.
13. The competent authority reserves the right to accept or reject any or all quotations, wholly or partly, without assigning any reason thereof.
14. The decision of the competent authority regarding the acceptance or rejection of the quotation shall be final and binding.


(Tashi Sangrup)
Assistant Registrar

Copy to :

1. Notice Board , Main Market.
2. Notice Board Administrative Block CIBS.
3. Official website of CIBS.
4. Accountant ,CIBS.
5. Concerned file.

Annexure-1

Name of the Work: BoQ for extension of the Ground near the Library Building of CIBS, Choglamsar, Leh

S.NO	Description of items	Quantity	Unit	Rate	Amount
1	Earth work in excavation by manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.	28.26	cum	647.61	18301.4586
2	Dumping stone excluding cost of stones.	5.65	cum	850	4802.5
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :	11.38	cum	9432.39	107340.5982
4	Random rubble masonry with hard stone from quarry in foundation and plinth level with cement concrete 1:6:12 at plinth with 1:6 mix	48.71	cum	6761.86	329370.2006
5	Providing and fixing up to floor five level precast cement Concrete solid block including hoisting and setting in position with cement mortar 1:3 (1 cement:3 coarse sand), with 6 mm thick cement plaster 1:3 (1 Cement: 3 fine sand) on exposed surface complete 1:3:6(1 cement :3 coarse sand : 6 graded stone)	13.13	cum	19534.88	256492.9744
6	15 mm thick cement plaster on rough side of single or half brick wall of mix 1:4(1 cement: 4 coarse sand)	68.95	sqm	424.32	29256.864
7	Finishing walls with water proofing cement paint of required shade on New work (two or more coats applied @ 3.84 kg/10sqm)	68.95	sqm	312.18	21524.811
8	UPVC pipe of 110 mm dia for rain water	45.72	rmt	900	41148
9	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	1822.50	cum	260.08	473995.8
10	Providing and laying 60mm thick factory made cement in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid joints with line sand etc. all complete as per the direction of Engineer-in-charge.	405.00	sqm	1475.06	597399.3
				Grand Total Amount	1879633